APPROACH PIPE (INCLUDED IN CULVERT SUMMARY RECAP)

STATION	BASIC BID ITEMS					PIPE OPTIONS in					END SECTIONS		linear feet		REMARKS
	CULVERT PIPE in	linear feet				STEEL - 2 2/3 x 1/2 CORR. 0.064 THK.	CONCRETE - CLASS 4	CONCRETE - CLASS 4	ALUMINUM - 2 2/3 x 1/2 CORR. 0.060 THK.	CORRUGATED POLY-ETHYLENE PIPE			HEIGHT OF COVER	CULVERT IN PL. in x ft	
		LENGTH OF PIPE	REMOVE PIPE CULVERT	RELAY PIPE CULVERT	CLEAN CULVERT PIPE						LEFT	RIGHT			
121+00	18	46				18		18	18		FETS	FETS	1.9		APP PIPE LT
121+00	18	50				18		18	18		FETS	FETS	2.3		APP PIPE RT
151+00	18	46				18		18	18		FETS	FETS	1.8		APP PIPE LT
156+50	24	48	45.2			24	24				FETS	FETS	1.0	16"X45.2'	APP PIPE RT
165+72	24	80	80.6			24		24	24		FETS	FETS	2.7	24" RCP X 80.6'	APP PIPE RT
165+72	18	46				18		18	18		FETS	FETS	1.5		APP PIPE LT
170+20			64.0											36"X64' RCP	EXIST. BLACK EAGLE RD LT TO ABANDON
195+50	18	50	56.0			18		18	18		FETS	FETS	1.5	18"X56'	APP PIPE LT
226+11	24	62	56.0			24		24	24		FETS	FETS	1.9	18"X56'	APP PIPE LT EMBRY RD
253+50	18	78	93.0			18		18	18	18	FETS	FETS	2.9	18"X93'	APP PIPE LT
258+00			81.0											18"X81'	APP PIPE LT
275+67.93	18	84	37.0			18		18	18	18	FETS	FETS	4.0	18"X37'	APP PIPE RT
278+70	24	66				24		24	24	24	FETS	FETS	2.4		APP PIPE LT ESSEX LN
332+24			46.0											18"X46'	APP PIPE LT
333+00	24	106				24		24	24	24	FETS	FETS	4.3		APPROACH PIPE LT-0+60 APP RT
398+25			56.0											24"X56'	EXISTING POWERLINE RD. TO ABANDON
408+00	24	104				24		24	24	24	FETS	FETS	4.0		APP PIPE RT POWERLINE RD
420+12	18	72				18		18	18	18	FETS	FETS	2.4		APP PIPE RT
420+12	18	72				18		18	18	18	FETS	FETS	2.4		APP PIPE LT
469+50	18	66				18		18	18	18	FETS	FETS	2.7		APP PIPE LT
TOTAL	~	~	615	0	0	~	~	~	~	~	~	~	~	~	

* COAT PIPE PER STANDARD SPEC. SEC. 709.__