MEDIAN INLETS

STATION	each				linear feet					cu. yards	REMARKS
	MEDIAN INLET		DROP INLET FRAME & GRATE	REMOVE DROP INLET	RCP		RCPA	24 " CSP 0.109" THK 2 2/3" X 1/2" CORR.	REMOVE PIPE CULVERT	FILL & ABANDON	
					CLASS 3	CLASS 4	CLASS 4				
	* TYPE 1	TYPE 2	TYPE 1		24"	24"	22" x 13½"				
2387+20.00		1		1	108.0				12.0	79	REMOVE INLET & 12.0' CSPA CULVERT RT. FILL & ABANDON, FETS. RT
2418+61.00	1			1				8.6	7.4		REMOVE 7.4' REPLACE W/ (2) 24" CSP 30° ELBOWS
2475+50.00								12.0	3.4		USE IN PLACE MEDIAN INLET REMOVE 3.4' & EXTEND 12.0' W/ FETS. RT.
2499+68.00	1			1		294.0		5.5	294.5		NEW TYPE I MEDIAN INLET W/ NEW 24" x 294.0' RCP (IRR.) 14.2' COVER W/FETS. LT. & RT.
2511+45.00	1			1				1.4	1.8		NEW TYPE I MEDIAN INLET - 109.51' LT.
2529+04.00			1								NEW TYPE I DROP INLET FRAME & GRATE - 107.34' LT. W / 2" RING ADJUSTMENT
2542+86.00								14.0			USE IN PLACE MEDIAN INLET NEW 24" x 14.0' CSP W/ FETS RT.
2555+00.00		1			102.0						NEW TYPE II MEDIAN INLET W/ NEW 24" x 102.0' RCP (IRR.) FETS RT. 5.5' COVER
2574+00.00			1	1							NEW TYPE I DROP INLET FRAME & GRATE, 15.86' RT.
2599+50.00		1			108.0						NEW TYPE II MEDIAN INLET W/FETS RT. - NEW 24" x 108.0' RCP (IRR.) 5.9' COVER
2614+31.00		1					90.0				NEW TYPE II MEDIAN INLET W/FETS RT. - NEW 22"x13½"x 90' RCPA, 4.0' COVER
2631+40.00	1			1							REMOVE & REPLACE WITH NEW MEDIAN INLET TYPE I
2657+92.00				1							REMOVE MEDIAN INLET 16.7' RT.
2657+94.00	1							2.2			NEW TYPE I MEDIAN INLET 10.0' RT AND CONNECT TO CULVERT
2670+75.00				1					2.7	44	REMOVE INLET & 2.7' RT. - FILL & ABANDON
2673+25.00		1			138.0						NEW TYPE II INLET W/ NEW 24" x 138.0' RCP (IRR.) FETS RT. 3.5' COVER
TOTAL	**5**	**5**	**2**	**8**	**456.0**	**294.0**	**90.0**	**43.7**	**322**	**123**	

* FIELD CAST CONCRETE COLLARS - SEE DETAILS