RANDOM RIPRAP

STATION		cu. yards		sq. yards		REMARKS
		RANDOM RIPRAP		GEOTEXTILE PERM. EROS. CNTRL. HIGH SURV. CLASS C	RIPRAP REVEGE-TATION	
FROM	TO	CL. 1	CL. 2			
1027+51.00			400.3	503	1,213	BRIDGE END
1028+48.95			656.7	850	1,990	BRIDGE END
1406+14.00			300.0			2.5' ON PIPE BOTTOM
1406+16.98	1406+47.13		240.0	345	721	OUTLET RIPRAP APRON LT.
1437+31.00			23.0	45	69	OUTLET RIPRAP APRON RT.
TOTAL		0.0	1,620.0	1,743	3,993	

RANDOM RIPRAP

STATION		cu. yards		sq. yards		REMARKS
		RANDOM RIPRAP		GEOTEXTILE PERM. EROS. CNTRL. HIGH SURV. CLASS C	RIPRAP REVEGE-TATION	
FROM	TO	CL. 1	CL. 2			
282+36		2.0				RIPRAP APRON LT.; CONN. FROM EX. RIPRAP TO CULVERT END
295+81		15.6		19		RIPRAP DRAIN CHUTE LT.
320+61	321+10		160.7	233	183	BRIDGE RIPRAP; SEE DETAIL
329+22		5.2		21		INLET AND OUTLET RIPRAP PROTECTION
338+00		2.5		10		INLET RIPRAP PROTECTION; RT.
355+61		1.7		9		INLET RIPRAP PROTECTION; RT.
TOTAL		27.0	160.7	292	183	