APPROACHES (FOR INFORMATION ONLY)

STATION	TYPE	linear feet				EXISTING SURFACING	feet		PROPOSED SURFACE	tons		cu. yards	sq. yards			gallons	REMARKS
		WIDTH	RADIUS #		LENGTH		PMS THK.	CAC THK.		EMULSIFIED ASPHALT CRS-2P	COMMER-CIAL MIX PG 58V-34	CRUSHED AGG. COURSE	COVER TYPE II	6" CONC.	AGG. TREAT.	EMULS. ASPHALT TACK	
			LEFT	RIGHT													
14+50	PRIVATE	20	0	0	49.7	CONCRETE			CONCRETE			14		86	86	7.0	RT.
15+29	PRIVATE	28	10	10	49.7	ASPHALT			ASPHALT	0.2	19	25	128		124	5.0	RT.
15+67	PRIVATE	16	10	10	49.7	GRAVEL			ASPHALT	0.2	14	18	94		90	7.0	RT.
18+49	PRIVATE	24	10	10	49.7	GRAVEL			ASPHALT	0.2	17	23	118		113	7.0	RT.
19+92	PRIVATE	24	15	25	53.6	GRAVEL			ASPHALT	0.2	19	23	132		114		RT.
SUBTOTAL	**PRIVATE**									**0.8**	**69**	**103**	**472**	**86**	**527**	**26.0**	
12+11	PUBLIC	32	25	25	50.1	ASPHALT			ASPHALT	0.3	48	79	190		216	10.0	RT. FLORA AVE
14+58	PUBLIC	32	25	25	50.3	ASPHALT			ASPHALT	0.4	50	77	197		212	11.0	LT. FLAGSTONE DR.
16+50	PUBLIC	32	25	25	49.7	ASPHALT			ASPHALT	0.5	65	105	258		292	14.0	RT. ALJEMA AVE.
SUBTOTAL	**PUBLIC**									**1.2**	**163**	**261**	**645**	~	**720**	**35.0**	

 # ALL RADII MEASURED TO FRONT OF GUTTER OR EDGE OF SHOULDER
M.O.C. - MEASURED ON CAD

APPROACHES (FOR INFORMATION ONLY)

STATION	TYPE	linear feet				EXISTING SURFACING	feet		PROPOSED SURFACE	sq. yards	tons			tons	cu. yards	sq. yards	gallons	REMARKS
		WIDTH	RADIUS #		LENGTH		PMS THK.	CAC THK.		COVER TYPE __	PLANT MIX BIT. SURF. __"	PLANT MIX BIT. SURF. MISC.	ASPHALT BINDER PG __-__	EMULS. ASPHALT CHFRS-2P	CRUSHED AGG. COURSE	AGG. TREAT.	EMULS. ASPHALT TACK	
			LEFT	RIGHT														
SUBTOTAL	FARM FIELD										~	0	0		0	0	0	
SUBTOTAL	PRIVATE										~	0	0		0	0	0	
SUBTOTAL	PUBLIC										0	~	0		0	0	0	

 # ALL RADII MEASURED TO FRONT OF GUTTER OR EDGE OF SHOULDER
M.O.C. - MEASURED ON CAD

APPROACHES (FOR INFORMATION ONLY)

STATION	TYPE	linear feet				EXISTING SURFACING	feet		PROPOSED SURFACE	sq. yards	tons	cu. yards	tons	gallons	sq. yards	REMARKS
		WIDTH	RADIUS #		LENGTH		PMS THK.	CAC THK.		COVER TYPE 1	COMMER-CIAL MIX PG 58V-34	CRUSHED AGG. COURSE	EMULS. ASPHALT CHFRS-2P	EMULS. ASPHALT TACK	AGG. TREAT.	
			LEFT	RIGHT												
31+65	FARM FIELD	24	25	25	66.4	GRAVEL	0.2	0.6	PAVED TO 12', GRAVEL TO LENGTH		8	54		3	66	LT., STAGECOACH TRAIL RD. ALIGNMENT
132+36	FARM FIELD	24	25	25	37.4	GRAVEL	0.2	0.6	PAVED TO 12', GRAVEL TO LENGTH		8	33		3	66	RT.
132+36	FARM FIELD	24	25	25	64.3	GRAVEL	0.2	0.6	PAVED TO 12', GRAVEL TO LENGTH		8	52		3	66	LT.
133+40	FARM FIELD	24	25	25	26.7	GRAVEL	0.2	0.6	PAVED TO 12', GRAVEL TO LENGTH		8	26		3	66	JOINT-USE FARM FIELD APP. RT.
245+27	FARM FIELD	24	25	25	33.3	GRAVEL	0.2	0.6	PAVED TO 12', GRAVEL TO LENGTH		8	31		3	66	LT.
SUBTOTAL	**FARM FIELD**									~	**40**	**196**	~	**15**	**330**	
133+70	PRIVATE	24	25	25	45.8	GRAVEL	0.2	0.6	PAVED TO R/W, GRAVEL TO END		18	36		8	150	LT., SKEW 15° RT., M.O.C.
248+91	PRIVATE	113	25	25	12.0	GRAVEL	0.2	0.6	PAVED TO 12', GRAVEL TO LENGTH		24	81		10	193	LT., M.O.C.
253+40	PRIVATE	30	25	20	65.2	GRAVEL	0.2	0.6	PAVED TO R/W (FULL LENGTH)		34	62		14	278	JOINT-USE PRIVATE APP. RT., M.O.C.
255+59	PRIVATE	24	20	20	29.8	GRAVEL	0.2	0.6	PAVED TO R/W, GRAVEL TO LENGTH		9	26		4	71	LT., M.O.C.
256+33	PRIVATE	15	25	25	39.8	GRAVEL	0.2	0.6	PAVED TO R/W, GRAVEL TO LENGTH		7	28		3	58	JOINT-USE PRIVATE APP. LT., M.O.C.
SUBTOTAL	**PRIVATE**									~	**92**	**233**	~	**39**	**750**	
250+89	PUBLIC	24	*	*	207.5	PAVED	0.2	0.6	PAVED	833	111	199	1.5	45	900	RT., STAGECOACH TRAIL RD., M.O.C.
SUBTOTAL	**PUBLIC**									**833**	**111**	**199**	**1.5**	**45**	**900**	
133+67	MAILBOX	6			212.5		0.2	0.6	PAVED	77	11	26	0.1	5	99	LT., M.O.C.
253+40	MAILBOX	6		25	36.2		0.2	0.6	PAVED	29	4	6	0.1	1	29	RT., M.O.C.
256+05	MAILBOX	6			212.0		0.2	0.6	PAVED	77	11	21	0.1	4	89	LT., M.O.C.
SUBTOTAL	**MAILBOX**									**183**	**26**	**53**	**0.3**	**10**	**217**	

 # ALL RADII MEASURED TO FRONT OF GUTTER OR EDGE OF SHOULDER
M.O.C. - MEASURED ON CAD
** SEE DETAILS*