WETLAND DELINEATION TABLE

WETLAND DESIGNATION	STATION		WETLAND AREA (acres)			REMARKS
			DELINEATED AREA	TEMPORARY IMPACTED AREA ##	PERMANENT IMPACTED AREA	
	FROM	TO				
WL-1	102+10	112+65	0.617			LT. - NO IMPACTS
WL-2A #	137+12	148+08	5.132		1.061	RT.
WL-2B	140+34	150+18	0.656		0.004	LT.
WL-2C	150+63	154+02	0.086			LT. - NO IMPACTS
WL-2D	154+44	165+14	1.220		0.019	LT.
WL-3	154+13	155+75	0.085		0.085	RT.
WL-4	176+97	185+83	0.672			LT. - NO IMPACTS
WL-5	190+03	195+76	0.153			LT. - NO IMPACTS
WL-6	197+44	199+21	0.219		0.219	RT.
WL-7A	198+82	222+95	3.626	1.255	0.583	LT.
WL-7B	207+64	210+86	0.055		0.055	RT.
WL-7C	207+49	210+92	1.039		0.194	RT.
WL-7D	211+57	220+08	0.845		0.402	RT.
WL-8A #	260+35	261+39	0.013	0.007	0.008	RT.
WL-8B #	260+59	261+70	0.012		0.002	RT.
WL-8C #	262+00	262+21	0.005			LT.
WL-9	284+67	285+25	0.017		0.015	RT.
WL-9A	288+33	324+19	2.663		0.868	LT. & RT.
WL-9B #	290+43	299+55	3.750	1.452	0.734	RT.
WL-11A	325+03	331+15	0.127		0.127	RT. - DITCH
WL-11B	332+34	337+65	0.149		0.149	RT. - DITCH
WL-12	333+13	333+93	0.058			LT. - NO IMPACTS
WL-13	366+90	369+11	0.206			RT. - NO IMPACTS
WL-14 #	377+89	384+13	1.730			RT. - NO IMPACTS
WL-15 #	386+45	396+37	2.523		0.097	RT.
WL-16A #	380+05	394+18	0.123		0.002	LT.
WL-16B	391+68	393+66	0.052			LT. - NO IMPACTS
WL-16C	395+20	397+70	0.152		0.089	RT.
WL-16D	395+06	397+22	0.074		0.008	RT.
WL-16E	398+07	398+26	0.006		0.006	RT.
WL17A	407+28	420+87	0.624	0.259	0.370	RT.
WL-17B	421+18	454+52	0.639		0.037	RT.
WL-18A	454+94	478+11	0.250		0.015	RT. - OLSEN CREEK
WL-18B	410+71	413+74	0.218		0.091	LT. - OLSEN CREEK
WL-19	478+32	481+75	0.301		0.228	LT.
WL-20	490+19	505+42	0.402		0.006	RT.
WL-21	495+43	505+17	0.643		0.263	LT.
WL-22A	505+30	505+52	0.003		0.002	LT.
WL-22B	505+39	505+61	0.006		0.004	LT.
WL-22C	505+58	506+23	0.003		0.003	RT.
WL-22D	505+67	506+30	0.004		0.004	RT.
WL-23	505+73	513+91	0.784		0.264	LT.
WL-24A	506+63	521+52	0.868		0.010	RT.
WL-24B	521+88	530+15	0.409	0.210	0.017	RT.
WL-24C	530+88	549+00	0.567		0.615	RT.
WL-24D	549+42	551+24	0.029		0.029	RT. - ROADSIDE DITCH
WL-24E	551+77	563+37	0.278		0.278	RT. - ROADSIDE DITCH
WL-24F	563+76	570+04	0.325		0.324	RT.
WL-24G	567+61	568+94	0.160		0.094	LT.
WL-24H	570+36	578+76	2.562		0.720	RT.
WL-24I	579+20	585+40	0.094		0.094	RT.
WL-25	541+44	545+15	0.186		0.028	LT. - ROADSIDE DITCH
WL-26	550+60	551+34	0.043		0.042	LT.
WL-27	561+53	563+64	0.139		0.082	LT.
WL-28	572+66	575+56	0.223		0.088	LT.
WL-29	577+29	578+61	0.041			LT. - NO IMPACTS
WL-30	589+40	590+67	0.091		0.034	LT.
WL-31A #	585+92	595+36	0.187		0.183	RT. - DAWKINS BRANCH
WL-31B #	593+89	594+25	0.005		0.005	LT. - DAWKINS BRANCH
WL-31C #	593+37	593+66	0.004		0.012	LT. - DAWKINS BRANCH
WL-31D #	593+64	594+46	0.010		0.004	LT. - DAWKINS BRANCH
WL-31E #	594+70	596+03	0.036		0.028	RT. - DAWKINS BRANCH
WL-32	601+25	602+13	0.038			LT. - NO IMPACTS
WL-33A #	602+84	603+62	0.476		0.275	RT.
WL-33B	607+91	608+73	0.070		0.038	RT.
WL-34	606+57	608+54	0.095			LT. - NO IMPACTS
WL-35A	609+16	613+12	0.087			RT. - NO IMPACTS
WL-35B	613+56	617+79	0.156		0.065	RT.
WL-36	609+48	617+68	0.447			RT. - NO IMPACTS
WL-37	615+91	616+97	0.037			LT. - NO IMPACTS
WL-38	618+43	621+81	0.133			LT. - NO IMPACTS
WL-39	623+35	624+87	0.052			LT. - NO IMPACTS
WL-40A	618+74	622+98	0.115	0.100	0.115	RT.
WL-40B	623+72	635+98	0.374		0.374	RT.
WL-40C	637+50	641+90	0.121		0.121	RT.
WL-40D	642+39	642+81	0.019		0.017	RT.
WL-41	631+88	635+96	0.117			LT. - NO IMPACTS
WL-42	638+67	646+18	0.852		0.157	LT.
WL-43	649+11	656+55	0.763			LT.
TOTAL			40.15	3.28	9.86	

 # AREA OF EXISTING WETLAND EXTENDS BEYOND PLAN LIMITS
TEMPORARY IMPACT AREAS ARE ESTIMATED AND PROVIDED FOR INFORMATIONAL PURPOSES ONLY. TEMPORARY WETLAND IMPACTS SHOWN IN THE TABLE AND ANY OTHER IMPACTS ASSOCIATED WITH CONTRACTOR OPERATIONS ARE TO BE PERMITTED BY CONTRACTOR.