WATER LINE

STATION		sq. feet	linear feet		pounds	each								REMARKS
		INSULATION	PVC PRESSURE WATER PIPE		DUCTILE IRON FITTINGS	CONNECT WATER LINE	WATER SERVICE *	ADJUST CURB BOX	RESET CURB STOP & BOX	ADJUST WATER VALVE BOX	RELOCATE WATER METER ##	ADJUST FIRE HYDRANT	RESET FIRE HYDRANT	
			CL. 150	CL. 200										
FROM	TO		10"	18"		6"								
649+20.80	649+75.60	766	56		760	2								92.3' RT. (SEE SADDLE/INSULATION DETAIL #3)
657+91.10		320											1	41.6' LT. (SEE INSULATION DETAIL #1)
657+91.50										1				38.0'LT.
658+00.00	658+80.00	640												LT. (SEE INSULATION DETAIL #1)
658+39.10		384												LT. (SEE INSULATION DETAIL #1)
659+76.30		320												LT. (SEE INSULATION DETAIL #1)
660+42.30		144									1			40.7' LT. (SEE INSULATION DETAIL #1 AND #2)
660+73.30		128												LT. (SEE INSULATION DETAIL #1 AND #2)
661+61.90		128												LT. (SEE INSULATION DETAIL #1 AND #2)
662+50.20											1			45.6' LT.
662+61.60									1					40.5' LT.
662+62.40		160							1					40.0' LT. (SEE INSULATION DETAIL #1 AND #2)
662+62.70											1			43.5' LT.
662+63.80											1			42.6' LT.
662+90.10		64												25.8' LT. (SEE INSULATION DETAIL #2)
663+06.30										1				30.7' LT.
663+16.40		64												39.1' RT. (SEE INSULATION DETAIL #2)
663+17.40		96												3.6' LT. (SEE INSULATION DETAIL #2)
663+26.00											1			41.3' LT.
663+26.80								1						39.6' LT.
663+29.90										1				37.9' LT.
663+30.10		64										1		39.7' LT. (SEE INSULATION DETAIL #2)
663+31.80										1				30.4' LT.
							2							
TOTAL		3,278	56	0	760	2	2	1	2	4	5	1	1	

100% STATE COST SHARE
INCL WATER METER
* INCL. CURB STOP BOX

SEE THIS EXAMPLE FOR: WATER MAIN

WATER MAIN #					
STATION		sq. feet	each		REMARKS
		INSULATION	ADJUST WATER MAIN	WATER MAIN CROSSING	
FROM	TO				
12+09.63		32	1		14.1 FT. RT.
13+56.56		32	1		9.0 FT. RT.
14+05.40		32	1		28.0 FT. LT.
15+30.00		32	1		2.8 FT. RT.
17+92.13		32		1	26.0 FT. LT.
17+64.86		32		1	2.1 FT. RT.
19+61.80		32		1	27.8 FT. LT.
20+25.02		32		1	0.2 FT. LT.
22+27.00		32	1		2.5 FT. RT.
22+97.69		32	1	1	23.0 FT. LT.
32+81.27		32	1		58.5 FT. LT.
33+22.38		32	1		56.0 FT. RT.
33+34.85		32	1		184.7 FT. RT.
35+06.00		32	1		7.0 FT. LT.
36+49.00		32	1		8.9 FT. LT.
39+80.29		32	1		11.0 FT. LT.
40+36.57		32		1	21.0 FT. RT.
41+67.00		32	1		11.2 FT. LT.
43+09.10		32	1		11.5 FT. LT.
49+07.45		32	1		6.6 FT. RT.
TOTAL		640	15	6	

 # 75% STATE COST SHARE AND 25% CITY OF BOZEMAN COST SHARE