CONCRETE BARRIER RAIL

STATION		each							REMARKS
FROM	TO	REMOVE CONCRETE BARRIER RAIL	CONCRETE BARRIER RAIL	TALL CONCRETE BARRIER RAIL	CONCRETE BARRIER RAIL TRANS.	ONE-WAY DEPART. CONC. BARRIER SECTION	RESET CONCRETE BARRIER RAIL	IMPACT ATTEN-UATOR __ BAY	
TOTAL		0	0	0	0	0	0	0	

CONCRETE BARRIER RAIL

STATION		each					REMARKS
FROM	TO	REMOVE CONCRETE BARRIER RAIL	CONCRETE BARRIER RAIL	TALL CONCRETE BARRIER RAIL	RESET CONCRETE BARRIER RAIL	CONCRETE BARRIER RAIL TRANS.	
115+55	132+46	169*		169	68	2	LITTLE PRICKLY PEAR CR.
161+41.95	167+07.26	57	57		57	2	SPRING CREEK INT.
230+78.38	233+36.51	25	25		25	1	LYONS CREEK
TOTAL		**251**	**82**	**169**	**150**	**5**	

* TALL BARRIER

SEE THIS EXAMPLE FOR: MODIFIED CONCRETE BARRIER RAIL & HAND RAIL

CONCRETE BARRIER RAIL

STATION		each			linear feet	REMARKS
FROM	TO	REMOVE CONCRETE BARRIER RAIL	MODIFIED CONCRETE BARRIER RAIL	IMPACT ATTEN-UATOR 6 BAY	HAND RAIL #	
37+40.54	38+40.54		10			NW OF NEW BRIDGE
37+40.64	38+39.04				98.4	NW OF NEW BRIDGE
46+95.39	48+65.47	13	2	1		NE OF NEW BRIDGE
46+96.89	47+33.99				37.1	NE OF NEW BRIDGE
TOTAL		13	12	1	136	

** FOR MODIFIED CONCRETE BARRIER RAIL DETAILS, SEE SHEET 23 AND BRIDGE PLANS DRAWING NO. SBR-BRR*

 # FOR HAND RAIL DETAILS, SEE SHEET 23 AND BRIDGE PLANS B64 & DRAWING NO. SBR-HND