MEDIAN CONCRETE CURB

STATION		linear feet		sq. yards		REMARKS
		MEDIAN CONCRETE CURB	REMOVE MEDIAN CURB #	CONCRETE		
FROM	TO	TYPE A		3"	6"	
46+06.86		33.8	33.8			DUAL DROP INLET APRON
50+46.93		25.2	25.2			DUAL DROP INLET APRON
55+76.00	64+26.00	1,705.8	1,705.8		433.8	6TH AVE N TO ARONSON - ISLAND, INCL 1-2.0' R NOSE, TIE INTO EXISTING MEDIAN
77+40.00	80+61.00	646.9	646.9		106.2	LAKE ELMO DR TO CVS - ISLAND, INCL 1-1.2' R NOSE, TIE INTO EXISTING MEDIAN
80+11.00	82+56.00	95.3	95.3		17.3	LAKE ELMO DR TO CVS - ISLAND, INCL 1-1.7' R NOSE, TIE INTO EXISTING MEDIAN
83+32.00	86+84.00	710.7	711.8		84.5	CVS TO LIBERTY ST - ISLAND, INCL 1-1.1' R NOSE
86+87.00	88+44.00	318.8	319.8		37.7	CVS TO LIBERTY ST - ISLAND, INCL 1-1.1' R NOSE
89+43.00	90+92.00	302.3	302.3		36.4	LIBERTY ST TO SONIC - ISLAND, INCL 1-1.1' R NOSES, TIE INTO EXISTING MEDIAN
94+08.00	96+60.00	513.2	513.2		72.8	SONIC TO ALBERTSONS - ISLAND, INCL 2-1.1' R NOSES
97+45.00	99+90.00	496.6	529.1		68.9	ALBERTSONS TO HANSEN LN - ISLAND, INCL 1-1.3' R NOSE
99+93.00	102+16.00	449.3	481.8		58.3	ALBERTSONS TO HANSEN LN - ISLAND, INCL 1-0.6' R NOSE
106+37.00	107+43.00	221.5	224.3		25.4	HILLTOP RD TO RADFORD SQ - ISLAND, INCL 1-1.0' R NOSE
107+46.00	107+78.00	68.9	70.4		9.3	HILLTOP RD TO RADFORD SQ - ISLAND
107+81.00	108+14.00	72.5	73.9		9.9	HILLTOP RD TO RADFORD SQ - ISLAND, INCL 1-1.3' R NOSE
108+88.00	113+29.00	890.4	920.1		116.1	RADFORD SQ TO MILTON RD - ISLAND, INCL 1-1.3' R, 1-1.1' R NOSES
114+18.00	115+68.00	308.1	321.3		38.7	MILTON RD TO SHAWNEE DR - ISLAND, INCL 1-1.2' R, 1-1.1' R NOSES
116+65.00	122+26.00	1,129.7	1,188.9	337.8	297.0	SHAWNEE DR TO JOSEPHINE DR - ISLAND, INCL 2-1.1' R NOSES
123+33.00	125+54.00	450.8	491.8		127.7	JOSEPHINE DR TO STADIUM CLUB - ISLAND, INCL 2-1.1' R NOSES
126+28.00	129+68.00	688.9	737.9		242.4	STADIUM CLUB TO U-HAUL - ISLAND, INCL 1-1.1' R, 1-1.4' R NOSES
130+74.00	135+41.00	941.4	961.0	96.7	246.6	U-HAUL TO LOGAN LN - ISLAND, INCL 1-1.0' R, 1-1.1' R NOSES
136+47.00	136+73.00	56.5	56.5		6.6	LOGAN LN TO JUDITH LN - ISLAND
136+77.00	137+12.00	74.6	74.6		8.8	LOGAN LN TO JUDITH LN - ISLAND
137+15.00	137+92.00	158.6	158.6		19.6	LOGAN LN TO JUDITH LN - ISLAND
137+96.00	141+26.00	668.0	687.8		179.5	LOGAN LN TO JUDITH LN - ISLAND, INCL 1-1.0' R NOSE
142+17.00	142+65.00	100.2	101.0		11.9	JUDITH LN TO ANCHOR AVE - ISLAND, INCL 1-1.1' R NOSE
142+68.00	143+42.00	154.3	155.1		18.5	JUDITH LN TO ANCHOR AVE - ISLAND, INCL 1-1.2' R NOSE
144+57.00	148+39.00	770.4	810.0	65.0	249.7	ANCHOR AVE TO SIOUX LN - ISLAND, INCL 2-1' R NOSES
149+45.00	154+13.00	942.7	982.1	263.0	264.8	SIOUX LN TO CROW LN - ISLAND, INCL 1-1.0' R, 1-0.9' R NOSES
155+10.00	158+29.00	645.2	665.1		47.5	CROW LN TO WICKS LN - ISLAND, INCL 1-0.6' R, 1-0.8' R NOSES
159+52.00	169+16.00	1,942.4	1,952.2	902.7	311.9	WICKS LN TO MATTSON LN - ISLAND, INCL 2-1' R, 1-40' R NOSES
169+27.00	176+11.00	1,377.6	1,411.7	113.0	299.3	MATTSON LN TO JAQUE LN - ISLAND, INCL 1-1.1' R, 1-1.4' R NOSES
177+26.00	180+50.00	659.7	751.0		218.9	JAQUE LN TO JERRIE LN - ISLAND, INCL 1-1.2' R, 1-1.8' R NOSES
181+54.00	184+76.00	656.5	690.4		219.0	JERRIE LN TO KATHY LN - ISLAND, INCL 1-1.1' R, 1-2.1' R NOSES
185+92.00	190+15.00	856.5	937.7	95.0	287.9	KATHY LN TO ROXY LN - ISLAND, INCL 1-1.2' R, 1-1.6' R NOSES
191+23.00	194+69.00	704.1	777.2		253.4	ROXY LN TO SHARRON LN - ISLAND, INCL 1-1.2' R, 1-2.0' R NOSES
195+75.00	200+37.00	940.4	969.8	401.2	252.5	SHARRON LN TO BILLINGS TOWING REPAIR - ISLAND, INCL 1-2.9' R, 1-2.0' R NOSES
201+25.00	208+69.00	1,496.8	1,558.2	352.2	378.1	BILLINGS TOWING REPAIR TO PEMBERTON LN - ISLAND, INCL 1-1.2' R, 1-1.0' R NOSES
SUBTOTAL		**22,274.6**	**23,093.6**	**2,626.6**	**5,056.9**	
TOTAL		**22,275**	~	**2,626.6**	**5,056.9**	

 # FOR INFORMATION ONLY, INCLUDE IN THE COST OF STREET EXCAVATION