SIDEWALK

STATION		sq. yards								linear feet	REMARKS
		CONCRETE SIDEWALK				DETECTABLE WARNING DEVICES		REMOVE SIDEWALK #		WIDTH	
		4"		6"		TYPE 1					
FROM	TO	LEFT	RIGHT	LEFT	RIGHT	LEFT	RIGHT	LEFT	RIGHT		
SUBTOTAL		0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	~	
TOTAL		0.0		0.0		0.0		~		~	

 # FOR INFORMATION ONLY - INCLUDE IN THE COST OF STREET EXCAVATION

SIDEWALK

STATION		sq. yards								linear feet	REMARKS
		CONCRETE SIDEWALK				DETECTABLE WARNING DEVICES		REMOVE SIDEWALK #		WIDTH	
		4"		6"		TYPE 1					
FROM	TO	LEFT	RIGHT	LEFT	RIGHT	LEFT	RIGHT	LEFT	RIGHT		
N ROUSE AVE.											
11+85.66	13+58.49			261.7		262.5		2.2		VARIES	INCL. 1-15' RADIUS
10+67.07	13+57.30				301.8		292.9		1.7	8.0	INCL. 1-10' TRANSITION & 1-20' RADIUS
14+38.43	15+77.45	136.1		14.7		232.5		2.2		VARIES	INCL. 1-25' RADIUS
15+77.45	17+28.29	110.8		29.4		147.0				5.0	INCL. 1-25' RADIUS AND EXT.
14+63.23	17+39.72		306.8				386.2		4.4	5.0	INCL. 1-35' & 1-25' RADII AND EXT.
18+14.18	32+33.61	830.1		112.7		333.3		4.4		5.0	INCL. 1-25' RADIUS AND EXT. & 1-30' RADIUS
18+22.71	32+60.50		834.6		165.7		974.7		4.4	5.0	INCL. 1-25' RADIUS AND EXT., 1-25',1-98' & 1-148' RADII
18+93.00	19+13.53				11.6					5.0	PRIVATE PARKING LOT AND TEXT
33+44.30	36+21.89	227.9		36.4		236.1		3.3		5.0	INCL. 1-25', 1-152.6' & 1-25' RADII AND EXT.
34+10.16	37+28.05		234.6		62.6		208.9		3.3	5.0	INCL. 1-37', 1-111' & 1-15' RADII
37+08.78	39+80.68	185.7		50.4		76.0		3.3		5.0	INCL. 2-25' RADII AND EXT.
37+85.97	39+88.84		128.2		59.4		2.2		3.3	5.0	INCL. 1-15' & 1-25' RADII AND EXT.
40+67.63	42+74.17	201.5		50.0		33.0		4.4		5.0	INCL. 1-25' RADIUS AND EXT., 1-45' & 1-138' RADII
40+66.23	43+23.19		174.8		60.5		93.7		3.3	5.0	INCL. 1-25' RADIUS AND EXT. & 1-33' RADIUS
44+48.59	53+03.41	494.9		197.5		145.7		2.2		5.0	INCL. 1-33', 1-98' & 1-225' RADII
44+99.07	47+06.30		173.5		25.0		3.2		3.3	5.0	INCL. 1-38', 1-138' & 1-25' RADII
47+90.35	53+94.92		323.5		179.5		110.8		3.3	5.0	INCL. 1-25', 1-35' RADII
55+17.58	55+35.35		10.4							5.0	
E MENDENHALL ST.											
10+12.36	10+62.81	48.3				48.3				8.6	
10+12.36	10+70.96		11.3		28.0		39.0			8.5	
11+50.97	13+52.75		132.3		52.4		162.1			8.2	
11+85.50	12+80.89	58.7				96.8				5.0	
12+80.89	13+52.75	39.6		14.2		68.4				VARIES	
E PEACH ST.											
11+02.76	12+99.39	101.9		7.2		168.4				5.0	INCL. 1-300', 1-533' RADII
11+02.76	13+04.63		108.8		25.7		119.8			5.0	
14+65.62	15+99.51		73.5				69.0			5.0	INCL. 1-8' TRANSITION
14+75.25	17+28.53	110.8		31.4		4.2				5.0	
E TAMARACK ST.											
10+36.78	12+31.07	83.5		24.4						5.0	INCL. 1-324' RADIUS
10+54.62	10+95.61		34.6				27.2			VARIES	
10+95.61	12+20.28		69.4				79.5			5.0	
13+35.10	15+68.61		110.8		28.2				1.1	5.0	INCL. 1-148' & 1-473' RADII
13+67.19	15+68.61	81.7		31.3						5.0	
E BIRCH ST.											
10+36.26	10+56.73	11.9				14.6		1.1		5.0	INCL. 1-104' RADIUS
SUBTOTAL		**2,723.4**	**2,727.1**	**861.3**	**1,000.4**	**1,866.8**	**2,569.2**	**23.1**	**28.1**	~	
TOTAL		**5,450.5**		**1,861.7**		**4,436.0**		~		~	

 # FOR INFORMATION ONLY - INCLUDE IN THE COST OF STREET EXCAVATION