CULVERT SUMMARY RECAP

BASIC BID	linear feet				cu. yards					each	sq. yards
	NEW PIPE (TOTAL)	RELAY PIPE CULVERT	CLEAN CULVERT PIPE	REMOVE PIPE CULVERT	FOUND-ATION MATERIAL	GRANULAR BEDDING MATERIAL	SPECIAL BACKFILL	CONCRETE - CLASS GENERAL	FILL & ABANDON PIPE	PLUG ENDS & ABANDON PIPE	GEOTEXT. STAB.
18 IN DR	610										
24 IN DR	466										
24 IN RCP	134										
54 IN RCP	142										
54 IN DR	134										
56 IN DR	100										
66 IN DR	184										
48 IN EQ DIA DR	90										
48 IN EQ DIA RCPA	212										
72 IN EQ DIA DR	100										
TOTAL	~	**0**	**0**	**1,491**	**309**	**385**	**0**	**28.2**	**0**	**0**	**1,929**

CULVERT SUMMARY RECAP

BASIC BID	linear feet		cu. yards					sq. yards
	NEW PIPE (TOTAL)	REMOVE PIPE CULVERT	FOUND-ATION MATERIAL	GRANULAR BEDDING MATERIAL	BEDDING MATERIAL	CONCRETE - CLASS GENERAL	SPECIAL BACKFILL	GEOTEXT. STAB.
18 IN DR	952							
18 IN RCP	468							
18 IN SOLID WALL HDPE	170							
24 IN DR	804							
24 IN RCP	70							
36 IN DR	426							
48 IN DR	114							
54 IN DR	116							
48 IN EQ DIA DR	86							
108 IN CSP	108							
9' x 5' RCB	78							
216 IN SSPP	172							
TOTAL	~	**1,410**	**848**	**767**	~	**44.9**	**575**	**3,083**