## GEOTEXTILE

| STATION | | linear feet | sq. yards | sq. yards | REMARKS |
|---|---|---|---|---|---|
| | | | GEOTEXT. STAB. | GEOGRID - BIAXIAL | |
| FROM | TO | | HIGH SURV. | | |
| 10+74.10 | 11+20.07 RR | 45.97 | | 213 | TYPICAL SECTION NO. 1 SUBEXC GEOTEXTILE * |
| 11+32.51 RR | 13+32.51 | 200.00 | | 925 | TYPICAL SECTION NO. 1 SUBEXC GEOTEXTILE * |
| 13+32.51 | 17+05.21 | 372.70 | | 1,723 | TYPICAL SECTION NO. 2 SUBEXC GEOTEXTILE * |
| | | | | | |
| SUBTOTAL | | ~ | 0 | 2,861 | NON-RESERVATION |
| | | | | | |
| 17+05.21 | 19+17.69 | 212.48 | | 982 | TYPICAL SECTION NO. 2 SUBEXC GEOTEXTILE * |
| 19+17.69 | 64+30.00 | 4,512.31 | 19,558 | 19,558 | TYPICAL SECTION NO. 3 |
| 50+88.00 | 56+12.00 | 524.00 | 888 | 888 | NORTH SCALE SITE SEE DETAIL |
| 64+30.00 | 67+37.00 | 307.00 | | 1,331 | TYPICAL SECTION NO. 3 SUBEXC GEOTEXTILE * |
| 67+37.00 | 74+79.05 | 742.05 | | 3,431 | TYPICAL SECTION NO. 2 SUBEXC GEOTEXTILE TIES INTO 30-YEAR BRIDGE END DESIGN * |
| 74+79.85 | 76+79.85 | 200.00 | | 925 | TYPICAL SECTION NO. 1 ** |
| 77+56.15 | 79+56.15 | 200.00 | | 925 | TYPICAL SECTION NO. 1 ** |
| 79+56.15 | 90+00.00 | 1,043.85 | 4,826 | 4,826 | TYPICAL SECTION NO. 2 |
| 90+00.00 | 196+22.89 | 10,622.89 | 46,044 | 46,044 | TYPICAL SECTION NO. 3 |
| 196+22.89 | 198+65.89 | 243.00 | | 1,123 | TYPICAL SECTION NO. 2 SUBEXC GEOTEXTILE * |
| 198+65.89 | 206+20.00 | 754.11 | | 3,249 | TYPICAL SECTION NO. 4 SUBEXC GEOTEXTILE * |
| 206+20.00 | 217+80.00 | 1,160.00 | 4,998 | 4,998 | TYPICAL SECTION NO. 4 |
| 217+80.00 | 221+70.00 | 390.00 | | 1,680 | TYPICAL SECTION NO. 4 SUBEXC GEOTEXTILE * |
| 221+70.00 | 225+42.30 | 372.30 | 1,604 | 1,604 | TYPICAL SECTION NO. 4 |
| 225+42.30 | 227+85.30 | 243.00 | 1,078 | 1,078 | TRANS. FROM TYP. SECTION NO. 4 TO TYP. SECTION NO. 2 |
| 227+85.30 | 265+02.00 | 3,716.70 | 17,184 | 17,184 | TYPICAL SECTION NO. 2 |
| 265+02.00 | 265+19.00 | 17.00 | 80 | 80 | TRANS. FROM TYP. SECTION NO. 2 TO TYP. SECTION NO. 6 |
| 265+19.00 | 267+54.94 | 235.94 | | 1,143 | TYPICAL SECTION NO. 7 ** |
| 268+14.74 | 270+51.00 | 236.26 | | 1,145 | TYPICAL SECTION NO. 7 ** |
| 270+51.00 | 270+68.00 | 17.00 | | 80 | TRANS. FROM TYP. SECT. NO. 6 TO TYP. SECT. NO. 2 30-YEAR BRIDGE END TIES INTO SUBEXC GEOTEXTILE * |
| 270+68.00 | 271+28.00 | 60.00 | | 277 | TYPICAL SECTION NO. 2 SUBEXC GEOTEXTILE * |
| 271+28.00 | 283+68.24 | 1,240.24 | 5,734 | 5,734 | TYPICAL SECTION NO. 2 |
| 283+68.24 | 286+38.24 | 270.00 | 1,196 | 1,196 | TRANS. FROM TYP. SECTION NO. 2 TO TYP. SECTION NO. 5 |
| 286+38.24 | 306+80.00 | 2,041.76 | 8,761 | 8,761 | TYPICAL SECTION NO. 5 |
| 306+80.00 | 307+84.65 | 104.65 | | 449 | TYPICAL SECTION NO. 5 SUBEXC GEOTEXTILE * |
| 307+84.65 | 310+54.65 | 270.00 | | 1,159 | TRANS. TYP. SECT. NO. 5 TO TYP. SECT. NO. 2 SUBEXC GEOTEXTILE * |
| 310+54.65 | 339+30.00 | 2,875.35 | 13,294 | 13,294 | TYPICAL SECTION NO. 2 |
| 339+76.00 | 343+00.00 | 324.00 | 598 | 598 | SOUTH SCALE SITE SEE DETAIL |
| 339+30.00 | 342+17.92 | 260.00 | | 1,480 | TYPICAL SECTION NO. 2 SUBEXC GEOTEXTILE * |
| 342+17.92 LT | 343+17.92 LT | 100.00 | | 116 | TRANS. TYP. SECT. NO. 2 TO TYP. SECT. NO. 8 LEFT SIDE SUBEXC GEOTEXTILE * |
| 342+17.92 RT | 343+00.00 RT | 82.08 | | 160 | TYPICAL SECTION NO. 2 RIGHT SIDE SUBEXC GEOTEXTILE * |
| 343+00.00 RT | 343+17.92 RT | 17.92 | | 34 | TRANS. TYP. SECT. NO. 2 TO TYP. SECT. NO. 8 RIGHT SIDE SUBEXC GEOTEXTILE * |
| | | | | | |
| SUBTOTAL | | ~ | 125,844 | 145,532 | RESERVATION |
| TOTAL | | ~ | 125,844 | 148,393 | |

* SEE SUBEXCAVATION SUMMARY FRAME FOR GEOTEXTILE QUANTITIES

** SEE BRIDGE END BACKFILL SUMMARY FRAME FOR GEOTEXTILE QUANTITIES