Quantities shown are preliminary and meant for planning purposes only.

Montana Department of Transportation
Preliminary Quantities

Proj Number: NH 38-1(17)0
MT-40 - US 93 TO DILLON ROAD
Prepared By:
Date:
UPN Number: 9187001
County: Flathead
Design Stage:
District: Missoula
CostEstimate: 9187001RDEST001
Type of Work:

Item Number	Quantity	Description	Unit
104030010	20,000.00	MISCELLANEOUS WORK	UNIT
108000010	1.00	STRUCTURE ANALYSIS	LS
109200005	1.00	MOBILIZATION	LS
201130005	0.40	CLEARING AND GRUBBING	ACRE
203020250	624.00	SPECIAL BORROW-EXCAVATION	CUYD
203020375	14,212.00	EMBANKMENT IN PLACE	CUYD
203080100	4,488.00	TOPSOIL-SALVAGING AND PLACING	CUYD
208010150	1.00	TEMPORARY EROSION CONTROL-LS	LS
208010200	500.00	TEMPORARY EROSION CONTROL-FIXED	UNIT
209010160	1.00	TEMPORARY SHORING	LS
301020254	415.00	BRIDGE END BACKFILL-TYPE 3	CUYD
301020340	9,289.00	CRUSHED AGGREGATE COURSE	CUYD
301020416	188.00	SHOULDER GRAVEL	CUYD
301020625	31,093.00	AGGREGATE TREATMENT	SQYD
401020046	307.00	PLANT MIX BIT SURF-MISC	TON
401020048	18,900.00	PLANT MIX SURF-1/2 IN	TON
401020300	269.00	HYDRATED LIME	TON
402020192	1,058.50	ASPHALT BINDER PG 58V-34	TON
402020315	10,268.00	EMULSIFIED ASPHALT-TACK COAT	GAL
402020320	6,125.00	EMULSIFIED ASPHALT-FOG SEAL	GAL
402020375	146.20	EMULSIFIED ASPHALT CHFRS-2P	TON
409000020	81,745.00	COVER-TYPE 2	SQYD
411010000	9,078.00	COLD MILLING	SQYD
411011135	4.60	RUMBLE STRIPS	MILE
411011145	0.70	SINUSOIDAL RUMBLE STRIPS	MILE
551020120	3.00	CEMENT GROUT	CUYD
552010160	755.00	BRIDGE DECK CRACK SEAL	SQYD
603010040	452.00	DRAINAGE PIPE 18 IN	LNFT
603010048	102.00	DRAINAGE PIPE 24 IN	LNFT
603010540	38.00	CSP 24 IN	LNFT
603012530	362.00	RCP 18 IN	LNFT
603013190	300.00	RCPA 18 IN EQ DIA	LNFT
603013202	74.00	RCPA 24 IN EQ DIA	LNFT
603013413	198.00	PIPE-CORR POLYETHYLENE DR 8 IN	LNFT

PRELIMINARY

Montana Department of Transportation

Preliminary Quantities

603587020	1,059.00	REMOVE PIPE CULVERT	LNFT
606010330	2,500.00	MGS GUARDRAIL	LNFT
606010335	5.00	MASH W-BEAM TERMINAL SECTION	EACH
606010342	4.00	MASH THRIE BEAM BR APPRCH SECTION	EACH
606010345	3.00	MGS ONE-WAY DEPARTURE TERMINAL SECTION	EACH
606010346	50.00	MGS INTERSECTING RDWAY TERMINAL SECTION	LNFT
606010370	50.00	RESET GUARDRAIL	LNFT
606010386	3,475.00	REMOVE AND SALVAGE GUARDRAIL	LNFT
606011503	2.00	RESET TEMP IMPACT ATTENUATOR	EACH
606011518	2.00	TEMPORARY IMPACT ATTENUATOR	EACH
608010020	11.60	SIDEWALK-CONCRETE 4 IN	SQYD
608010050	51.60	SIDEWALK-CONCRETE 6 IN	SQYD
608010125	4.40	DETEC WARNING DEVICES-TYPE 1	SQYD
609010112	34.00	CURB 4 IN-CONCRETE	LNFT
609010160	2.80	GUTTER-CONC VALLEY	SQYD
609010200	112.00	CURB AND GUTTER-CONC	LNFT
610100101	2.30	SEEDING AREA NO 1	ACRE
610100102	0.20	SEEDING AREA NO 2	ACRE
610100103	6.00	SEEDING AREA NO 3	ACRE
610100326	2.30	FERTILIZING AREA NO 1	ACRE
610100327	0.20	FERTILIZING AREA NO 2	ACRE
610100555	8.20	CONDITION SEEDBED SURFACE	ACRE
610220100	0.20	MULCH	ACRE
618030015	500.00	TRAFFIC CONTROL-FIXED	UNIT
618030075	92.00	TRAFFIC CONTROL-DAY	DAY
618030230	1.00	TRAFFIC CONTROL PLAN	LS
618040030	92.00	FLAGGER-SHIFT	EACH
618040040	46.00	PILOT CAR-SHIFT	EACH
618100001	4.00	MOTORCYCLE ADVISORY SIGN	EACH
618100005	4.00	PORTABLE VARIABLE MESSAGE SIGN	EACH
618190100	200.00	TEMPORARY BARRIER RAIL	LNFT
618190110	200.00	RESET TEMP BARRIER RAIL	LNFT
620011105	8.00	WORDS AND SYMBOLS-WHITE PAINT	GAL
620011110	10.00	WORDS AND SYMBOLS-YELLOW PAINT	GAL
620011260	5.00	WORDS AND SYMBOLS-WHITE EPOXY	GAL
620011265	6.00	WORDS AND SYMBOLS-YELLOW EPOXY	GAL
620012955	33,608.00	TEMPORARY STRIPING	LNFT
620013000	222.00	STRIPING-WHITE PAINT	GAL
620013960	148.00	STRIPING-WHITE EPOXY	GAL
620014000	232.00	STRIPING-YELLOW PAINT	GAL

PRELIMINARY

Montana Department of Transportation
Preliminary Quantities

620014960	154.00	STRIPING-YELLOW EPOXY	GAL
622011084	1,177.00	GEOTEXTILE STABILIZATION	SQYD
622011086	428.00	SEPARATION GEOTEXTILE - HIGH	SQYD
623000180	27.00	MAILBOX-LARGE	EACH

PRELIMINARY

Montana Department of Transportation
Preliminary Quantities

Proj Number:	NH 38-1(17)0 MT-40 - US 93 TO DILLON ROAD	**Prepared By:**	state\U2948
		Date:	10/21/2022 1:30:26 PM
UPN Number:	9187001	**County:**	Flathead
Design Stage:	Final Plan Review	**District:**	Missoula
CostEstimate:	9187001ELEST001	**Type of Work:**	

Item Number	Quantity	Description	Unit
109200005	1.00	MOBILIZATION	LS
616323124	40.00	CONDUIT-STEEL 2 1/2 IN RIGID	LNFT
616343920	300.00	CONDUIT-PLASTIC 2 IN	LNFT
616343924	32.00	CONDUIT-PLASTIC 2 1/2 IN	LNFT
616343930	270.00	CONDUIT-PLASTIC 3 IN	LNFT
617000000	8.00	FOUNDATION-CONCRETE	CUYD
617033414	630.00	CABLE-COPPER 7AWG14-600V	LNFT
617033614	60.00	CABLE-COPPER 12AWG14-600V	LNFT
617123108	65.00	CONDUCTOR-COPPER AWG8-600V	LNFT
617123110	250.00	CONDUCTOR-COPPER AWG10-600V	LNFT
617303300	1.00	HIGH EFFICACY LUMINAIRE LED	EACH
617503130	1.00	SIG-TRAF 3 COL-1 WAY 12-12-12	EACH
617513125	1.00	SIG TRAF 4 COL 1 W 12-12-12-12	EACH
617523127	1.00	SIG-TRAF 5 COL-1 W 12-12-12-12	EACH
617553020	6.00	SIG-PEDESTRIAN TYPE 2	EACH
617673100	4.00	SIG STANDARD TYPE 1-100	EACH
617713097	1.00	SIG STANDARD TYPE 3-A-900-7	EACH
617763500	4.00	DETECTOR-RADAR/PRESENCE	EACH
617763510	2.00	DETECTOR-RADAR/ADVANCE	EACH
617781000	1.00	REMOVE AND SALVAGE MISC ELECTRICAL	LS
617783030	1.00	REMOVE AND RESET MISC ELECTRICAL	LS
617903255	6.00	PUSH BUTTON-PEDESTRIAN-TACTILE	EACH
617903502	100.00	EMER PRE-EMPTION DET CABLE	LNFT

PRELIMINARY

Montana Department of Transportation
Preliminary Quantities

Proj Number:	NH 38-1(17)0 MT-40 - US 93 TO DILLON ROAD	**Prepared By:**	state\U4821
		Date:	9/29/2026 2:22:00 PM
UPN Number:	9187001	**County:**	Flathead
Design Stage:	Final Plan Review	**District:**	Missoula
CostEstimate:	9187001SIESTZ01	**Type of Work:**	

Item Number	Quantity	Description	Unit
109200005	1.00	MOBILIZATION	LS
619010062	31.30	SIGNS-ALUM SHEET INCR XI	SQFT
619010090	462.30	SIGNS-ALUM REFL SHEET XI	SQFT
619010230	43.00	REMOVE SIGN	EACH
619010240	2.00	REMOVE SIGN-GUIDE	EACH
619010310	18.00	POSTS-STEEL U SIGN	LB
619010320	325.00	POSTS-STEEL STRUCTURAL SIGN	LB
619010450	26.00	POLES-TREATED WOOD 4 IN	EACH
619010460	22.00	POLES-TREATED WOOD 5 IN	EACH
619010720	4.00	FRANG SIGN POST BKWY-S3 X 5.7	EACH
619011090	104.00	DELINEATOR TYPE 1	EACH
619011095	11.00	DELINEATOR TYPE 2	EACH

PRELIMINARY